December 10, 2012

Report



Address Any City, Ky.

Prepared for Client

B and **B** Inspections

48 Trapper Way Bowling Green, KY 270-202-2908

email: <u>BandBinspections@insightbb.com</u>
website: <u>http://BandBInspections.Home.insightBB.com</u>

Serving All Kentucky

December 10, 2012

Definitions

All directions are given as if the main front door is being viewed from the front, facing the front.

NOTE: All definitions listed below refer to the property or item as inspected on this report at the time of inspection.

Conditions: Description:

Functional Item appears to be Functional with no obvious signs of defect.

NI Not Inspected Item was unable to be inspected for safety reasons, due to lack of power,

inaccessible, disconnected at time of inspection, or seasonal impediments.

NP Not Present Item does not exist in the structure inspected.

Conditional Item appears to be performing its intended function, but is in need of minor repair.

Defective Item appears to be sufficiently deficient; unsafe; hazardous or inoperative.

General Information

Property Information

Address Address

City State Ky. Zip

Contact Name

Phone E-Mail

Client Information

Client Client

Address

City State Zip

Phone E-Mail

Inspector Information

Inspector Peter Brandt

Company B and B Inspections, LLC

Address 48 Trapper Way

City Bowling Green State Ky. Zip 42103

Phone 270-202-2908 Fax 270-842-5785

E-Mail BandBInspections@InsightBB.com

License #: HI2478 Signed: Peter Brandt

Conditions

Others Present

Estimated Age 1963 Property Occupied No

Inspection Date 12/7/2012 Temperature 53F Weather Scattered showers

Start Time 7:30am End Time 6:30pm

Inspection Date 12/8/2012 Temperature 54F Weather Cloudy

Start Time 6:50am End Time 2:45pm

Soil ConditionsWetElectric OnYesGas/Oil OnYesEntrance FacesSoutheastSpace Below GradeSlab

Building Type Industrial Site

Sewage DisposalCityHow Verified Verified on Site DrawingWater SourceCityHow Verified Inspectors knowledge

Additions/Modifictns Several since early 1960's How Verified PVA website listed 8 different square footage

areas.

Page 2 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Table of Contents

Definitions	page 2
General Information	
Conditions:	4
Exterior Surface and Components	7
Roof	10
Structure	12
Electrical	14
Heating and Air Conditioning Systems(54)	19
Warehouse Heating Units(18)	45
Plumbing17 BathsWater heaters	46
Interior rooms	55
Accessories: Elevator	58
Fire Alarm System	59
Sprinkler System	60
Limitations	61
Summaries: Conditional Items	63
Defective Items	67

Client: Client

Site

Building perimeter, land grade, and water drainage directly adjacent to the foundation. Trees and vegetation that adversely affect the structure. Walks, grade steps, driveways, patios, and retaining walls contiguous with the structure. Describe the type of material and inspect the condition of the parking lot, drives, walkways, grade steps, patios, and other items contiguous with the inspected structure. Observe the drainage, grading, and vegetation for conditions that adversely affect the structure.

Condition: Items:

Conditional Surface drainage: Some underground drain tiles, and some takeaways. Rear left corner

has erosion. A drain tile has been installed to prevent further erosion.

Front ditch has a holes developing between drain grates.

Defective Vegetation: Bushes, grass. Tree causing damage to fascia between HR and Sales

areas. Fascia supports broken, and no longer secure.

Conditional Vegetation: Two areas on the left side have trees left in piles.

Conditional Lot: Asphalt/concrete. Adequate. Evidence from all the construction

phases exist. Two rubble piles exist on the left side, one on rear side.

ConditionalWalks, steps:Concrete.Some demolition areas not completed, right and left sides.ConditionalPatio drainage:Concrete.Left side demolition area has no smooth access to the

overhead door area. Does not drain.

ConditionalRetaining Wall: Brick. Corner near front door has loose and cracked bricks.

Functional

Gas Meter: At Engineering building, front side, reading 15161 mcf.

At Front warehouse, left front, meter reading 98277 mcf.

Defective Outdoor lighting: One wallpack for the side walls/doors functioning of at least 16.

One building mounted flood functioning of at least 11.

Two poles with mounted flood lights functioning of at least 4 poles. Pole on left side leaning and conduit damaged. Lot light aiming to roof.

NP **Signage:** NP

Functional **Bollards:** Adequate

Conditional Fence: All fencing needs maintenance and repair. The one place where the

fence is next to the building structure, the fence is leaning. All other

areas are not contiguous with the structure.

Functional Chiller: Not connected inside. Appears whole and intact. Not tested.

Rear left corner has erosion. A drain tile has been installed to prevent further erosion.

Tree causing damage to fascia between HR and Sales areas. Fascia supports broken, and no longer secure.





Page 4 of 70

Client: Client File

File: SampleIndustrialInspectionReport

December 10, 2012

Some demolition areas not completed, right side.

Evidence from all the construction phases exist.




Corner near front door has loose and cracked bricks.

Pole on left side leaning and conduit damaged.





The one place where the fence is next to the building structure, the fence is leaning.








December 10, 2012

Two rubble piles exist on the left side, one on rear side.








Front ditch has a hole developing between drain grates.



Lot light aiming to roof.



Page 6 of 70

Client: Client File: SampleIndustrialInspectionReport

Exterior Surface and Components

Visible structural components. Wall covering, trim, and protective coating. Windows and doors. Attached porches, decks, steps, balconies, handrails, guardrails, and carports. Describe the type and material comprising the exterior components inspected. Observe the condition of the components from the ground level. Observe the condition of a representative number of visible windows and doors. Inspect attached porches, decks, steps, balconies, handrails, and guardrails.

Condition: Items:

NI

Conditional Outside Covering: Metal siding, brick. Left side near the inclined ramp damaged.

Left side rusting at bottom.

Functional Outside Covering: Near the front door, EIFS. Exterior Insulated Finishing System.

Internal of the EIFS: Exterior inspected only. This siding system often develops

internal moisture. This is not a part of this inspection.

Conditional Trim/Fascia/Soffit: The fascia near between the HR and Sales areas sited earlier.

Above the gas meter at the engineering front wall soffit pieces

missing. Awning at left Sales door damaged.

ConditionalOutside Doors:Some are chained shut that do not close securely.ConditionalOverhead Doors:Several bumpers missing, damaged, rear side.

Conditional Windows: Fixed, sliding, tilt.

Tilting window near fence left front was not closed.

ConditionalPatio:Concrete. Right side missing standard steps.DefectiveSteps/rails:Rails missing for the right side patio.

Defective Electric: Electrical outlets left side not functioning.

Outlet near engineering AC units not GFCI protected.

Extension cord near guard shack powered and not GFCI

protected.

Defective Hose bibs: Hose bibs had no water left side.

Defective Misc.: Indoor ceiling insulation should not be used outside.

Defective Misc.: Side exhaust vent bent mount on right side.

Left side rusting at bottom.

Left side near the inclined ramp damaged.





Page 7 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Above the gas meter at the engineering front wall soffit pieces missing.

Tilting window near fence left front was not closed.





Several bumpers missing, damaged, rear side.



Right side missing standard steps.





Rails missing for the right side patio.

Page 8 of 70


Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Awning at left Sales door damaged.



Extension cord near guard shack powered and not GFCI protected.



Indoor ceiling insulation should not be used outside.



Page 9 of 70

Client: Client File: SampleIndustrialInspectionReport

Roof

Roof covering material. Rain gutter and downspout system. Visible portions of roof flashings. Roof ventilation. Roof soffits and fascias. Roof skylights and other roof accessories. Describe the type of roofing and gutters. Observe the condition of visible roof material, rain gutter and downspout systems, visible portions of roof flashings, roof soffits and fascias, roof vents, skylights and other roof accessories visible from the exterior. Inspect flat roofs where internal accessibility is readily and safely available. Report presence of roof ventilation.

Type: Flat, approximately 1/2 inch slope per 12 inches.

Method of Inspection: On the roof.

Approximate Age: Various. Ranges from 2 years (3/4 of warehouse) to 48 years.

Condition: Items:

Functional Roof covering: Metal over all but the paint area. The paint area has Mineral Surface

Roll Roofing. Small hail dents apparent on the Engineering roof.

No functional degradation apparent from these hail dents.

Defective Roof covering: An active leak was found in the HR near the sink area with a

first aid area.

Conditional Gutters/downspouts: Internal Drains between warehouses. Exterior metal gutters with

metal downspouts all other areas. Hail dents apparent on rear

facing surfaces.

The gutters could easily gather debris to the right of the front door

and then water would leak into the office area.

The rear gutter on the rear warehouse had debris through most of the

length of the building.

The gutter between warehouses had debris on the left side.

Functional Flashing: Metal/rubber.

Defective Ventilation:One powered vent on the Engineering roof cover off and not functional. **Conditional**Soffit/fascia:
The metal fascia noted in the Site Section between HR and Sales.

NP Skylights: NP

Conditional Misc.: Cleanup of unused, unattached metal siding from recent repairs

was not done to the left of the front door.

The rear gutter on the rear warehouse had debris through most of the

Hail dents apparent on rear

length of the building.





Page 10 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

first aid area. /


The gutters/roofing could easily gather debris to the right of the front door and then water would leak into the office area.







The gutter between warehouses had debris on the left side.



Cleanup of unused, unattached metal siding from recent repairs was not done to the left of the front door





One powered vent on the Engineering roof cover off and not functional.



Page 11 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Structure

Foundation walls, first-floor systems, other support and sub-structure components, stairs. Ventilation (when applicable). Grade slab and/or floor slab. Describe the type of structure and material comprising the structure and other items inspected. Observe the condition and serviceability of visible, exposed areas of foundation walls, grade slab, bearing walls, posts, piers, beams, joists, trusses, subfloors, stairs, and other similar structural components. Inspect foundations for indications of flooding, moisture, or water penetration. Operate the sump pump when present. Inspect the visible and accessible structure members. Observe the visible condition of floor slab when present.

Condition: Items:

Functional Structure Type: Metal columns and beams. Metal siding on all but offices. Offices

have brick siding.

Defective Structure: Warehouse column damage exists on about 14 columns. Starting

at the right front with column A1, and proceeding to I15 at the rear left corner, A1, A4, A8, A9, C14, F4, F12, G14, H6, have holes mostly from fork trucks. The concrete is likely no longer secure under columns G1, G5, H6. Beams are rusted at the bottom to the point of not providing the intended strength at columns C15, E15, I7,

and the front right column of the front warehouse.

Functional Foundation: Concrete

Functional Differential Movement: None noted. One small vertical crack noted on the rear wall of the

indoor truck unloading ramp. Monitor for change.

Functional Floor/Slab: Concret

Functional Sub floor: Concrete first floor. Second floor engineering metal structure.

Defective Moisture: Staining noted in many areas from prior roof leaks, gutters formerly full of

debris, and AC vents being closed. These all appeared inactive. Several actively wet areas were apparent. One from an AC condensate drain, not covered in this section. Several were from plumbing, not

covered in this section.

The OSB wood wall at the rear of the second warehouse was holding as much moisture to peg my moisture meter. This is likely from the debris

in the gutters allowing the water to drain into the wall.

Functional Sump pump: Operational. First floor of Engineering section.

An example of a damaged column.



Page 12 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

An example of damaged concrete under a column.



The OSB wood wall at the rear of the second warehouse was holding as much moisture to peg the moisture meter (above 44%). An example of a rusted through column at the bottom.

Client: Client





Electrical

Entrance of the primary service from masthead to main panel. Main and sub-panels including feeders. Branch circuits, connected devices, and lighting fixtures.Describe the type and location of primary service (overhead or underground), voltage, amperage, and over-current protection devices (fuses or breakers). Observe the existence of a connected grounding conductor when readily accessible. Inspect the main and branch circuit conductors for proper over-current protection and condition by visual observation after removal of the readily accessible main and sub electric panel cover(s). Verify operation of a representative number of accessible switches, receptacles and light fixtures. Verify grounding and polarity of a representative number switches, receptacles and light fixtures. Verify grounding and polarity of a representative number of receptacles in proximity to plumbing fixtures or on the exterior. Verify operation of ground fault circuit interrupters (GFCI), if present. Observe the general condition of visible branch circuit conductors that may constitute a hazard to the occupant or the structure by reason of improper use or installation of electrical components.

Outside Equipment

Service: Overhead Volts: Transformed to voltages to 4 main panels

Starting from the rear, going forward, these 4 will be called: Rear Square D

Rear Federal Pacific Front Federal Pacific Front Underground

Condition: Items:

Functional On pole on left side. Current usage 38616kwh, load 0.08kw. Meter: Conditional


On left middle side one transformer is not connected, and two **Out of service equipment:**

transformers have the fused knife switches disconnected. Conditional **Possible 5th service point:** Near the left front corner of the property, a feed exists that

goes underground. I could not locate another main in the plant for

this feed. This pole likely feeds the transformer to the left

of HR offices.



On left middle side one transformer is not connected, and two transformers have the fused knife switches disconnected.

Page 14 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Rear Square D Main Panel

Service Size: 600 Amp Volts: 480/277 3 phase

Main Panel Location: Rear warehouse left wall.

Condition: Items:

Functional Service: Overhead Functional Main Panel Manufacturer: Square D Functional Max Capacity: 600 Amp Functional Main Breaker Size: 600 Amp

Functional Transformers: Mounted on pole outside left warehouse wall.
Functional Breakers/Fuses: One main, 7 breaker ranging from 30 to 225 amps.

Functional Drip Loop/Weather head: Adequate

Functional Ground: Ground cable at pole to ground.

Functional Labels: Labeled adequately.

Defective Subpanels: Subpanel B and panel to the rear of Panel A missing covers.

Panels throughout this plant are lacking covers. Many missing complete front panels. Many electrical enclosures are not covered.

These occurrences are too extensive to list.

Subpanel B and panel to the rear of Panel A missing covers.





Page 15 of 70

Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Rear Federal Pacific

Service Size: 800 Amp Volts: 120/240

Main Panel Location: Front warehouse left wall.

Condition: Items:

Defective Service: Overhead. Fused disconnect switch blown.

Functional Main Panel Manufacturer: Federal Pacific Functional Max Capacity: 800 Amp

Defective Main Breaker Size: Not present

Section 230.70(A)(1) is as follows: "The service disconnecting means shall be installed at a readily accessible location either outside of a building or structure or inside nearest the point of entrance of the service conductors." The fused pole mounted knife switches are the only way to disconnect this panel.

Functional Transformers: Mounted on pole outside left warehouse wall.

Conditional Breakers/Fuses: No main, 10 breakers. Shield missing on 2 breakers.

Functional Drip Loop/Weather head: Adequate

Functional Ground: Ground cable at pole to ground.

Conditional Labels: One breaker not labeled.

Defective Subpanels: Panels throughout this plant are lacking covers. Many missing

complete front panels. Many electrical enclosures are not covered.

These occurrences are too extensive to list.

Main Breaker not present:



One breaker not labeled.



Fused disconnect switch blown.

Shield missing on breakers.

Page 16 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Front Federal Pacific

Service Size: 1600 Amp Volts: 480/277 3 phase

Main Panel Location: Front warehouse left wall.

Condition: Items:

Functional Service: Overhead
Functional Main Panel Manufacturer: Federal Pacific
Functional Max Capacity: 1600 Amp
Defective Main Breaker Size: Not present

Section 230.70(A)(1) is as follows: "The service disconnecting means shall be installed at a readily accessible location either outside of a building or structure or inside nearest the point of entrance of the service conductors." The fused pole mounted knife switches are the only way to disconnect this panel.

Functional Transformers: Mounted on pole outside left warehouse wall.

Functional Breakers/Fuses: No main, 5 breakers.

Functional Drip Loop/Weather head: Adequate

Functional Ground: Ground cable at pole to ground.

Conditional Labels: 3 of 5 breakers not labeled.

DefectiveSubpanels:
Panels throughout this plant are lacking covers. Many missing

complete front panels. Many electrical enclosures are not covered.

These occurrences are too extensive to list.

Main Breaker not present:



3 of 5 breakers not labeled.

Page 17 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Front Underground

Service Size: 1200Amps Volts: Most likely 480/277 3 phase

Main Panel Location: Rear warehouse left wall.

Condition: Items:

Functional Service: Underground
Functional Main Panel Manufacturer: Square D
Functional Max Capacity: 1200Amps
Functional Main Breaker Size: 1200Amps

Functional Transformers: Mounted on pole outside left warehouse wall.

Functional Breakers/Fuses: One main, 5 breakers

NP Drip Loop/Weather head: Underground

Functional Ground: Ground cable at pole to ground.

Functional Labels: 1 of 5 not labeled.

Functional Subpanels: Likely more adequate than rest of plant, being the newest of the

feeds.

Page 18 of 70 Client: Client File: SampleIndustrialInspectionReport

Heating and Air Conditioning Systems

Describe the type of fuel, heating/cooling equipment, and heating/cooling distribution system. Operate the system using normal readily accessible control devices. Open readily accessible access panels or covers provided by the manufacturer or installer, if readily detachable. Observe the condition of normally operated controls and components of the systems. Observe visible flue pipes, dampers and related components for functional operation. Observe the condition of a representative number of heat/cool sources in each habitable space of the house. Inspect the operation of fixed supplementary heat units.

Heating and Air Conditioning Systems

General Items

Condition: Items:

Defective

Hail Damage: Most AC units have hail damage. The fins that face the rear of the

building on most of the units have hail damage.

Conditional Gas heater plumbing: Several offices connected, many not.

Capped off. Gas line ran.





Rear Warehouse Break Room

Location Label Roof:D4Approximate Age:10 yearsLocation Label Thermostat:D4Capacity:1.5 ton cooling.

Manufacturer:No name foundTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:20F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC drain.

Functional Thermostat: 1st floor breakroom.

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Adequate

Page 19 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Rear Warehouse Break Room

Location Label Roof:E4Approximate Age:10 yearsLocation Label Thermostat:E4Capacity: 5 ton cooling.

Manufacturer: Bryant Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: Defective

Condition: Items:

Defective Heat Operation: Would not turn on.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC drain.

Functional Thermostat: Left stairway to second floor.

Functional Flue Pipe: Metal Functional Flue Lines: Metal

Defective Filter: No filter appeared to be present for this system

Rear Warehouse Break Room

Location Label Roof: NP, very likely 4F Approximate Age: 15 years Location Label Thermostat: 4F Capacity: 5 ton cooling.

Manufacturer: If F4: Bryant Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: Defective

Condition: Items:

Defective Heat Operation: Would not turn on.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC drain.

Functional Thermostat: Left stairway to second floor.

Functional Flue Pipe: Metal Functional Flue Lines: Metal

Defective Filter: No filter appeared to be present for this system

To right of second warehouse break room

Location Label Roof:No labelApproximate Age:20 yearsLocation Label Thermostat:None foundCapacity: Approx.1.5 ton cooling.

Manufacturer: Ruud Temperature Differential Cooling: NI Fuel: Electric/? Temperature Differential Heat Mode: NI

Condition: Items:

NI Heat Operation: Not found. Likely abandoned and replaced with unit D4.

NI A/C System Not found Not found Functional **Condensate Removal:** Functional Thermostat: Not found Functional Flue Pipe: Not found **Functional** Flue Lines: Not found Functional Filter: Not found



Page 20 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Front warehouse second floor office area

Location Label Roof: Not labeled Approximate Age: 15 years
Location Label Thermostat: 4B Capacity: Approx. 3 ton cooling.

Manufacturer: No page found Temperature Differential Cooling.

Manufacturer: No name found Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: 22F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to condensate pump to hose to roof.

Functional Thermostat: 2nd floor main room.

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Clean

Conditional Electric: Disconnect not mounted properly.

Front warehouse, front office area

Location Label Roof: Not labeled Approximate Age: 15 years
Location Label Thermostat: 3A Capacity: Approx. 1.5 ton cooling.

Manufacturer: Heil Temperature Differential Cooling:
Fuel: Electric/gas Temperature Differential Heat Mode:

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

NΙ

15F

Functional Condensate Removal: PVC to drain.
Functional Thermostat: Press office
Functional Flue Pipe: Metal

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Adequate

Front warehouse, front office area

Location Label Roof:Not labeledApproximate Age:15 yearsLocation Label Thermostat:9Capacity: Approx. 3 ton cooling.Manufacturer:None foundTemperature Differential Cooling:

Manufacturer: None found Temperature Differential Cooling: NI Fuel: Electric/gas Temperature Differential Heat Mode: 15F

Condition: Items:

Defective Heat Operation: Would not turn on.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

Functional Thermostat: Old IT office hallway.

Functional Flue Pipe: Metal Functional Flue Lines: Metal

Conditional Filter: Wadded up in slot

Page 21 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Front warehouse, front office area

Location Label Roof: Not labeled Approximate Age: 10 years Capacity: Approx. 3 ton cooling. **Location Label Thermostat:** Not labeled **Temperature Differential Cooling:** Manufacturer: No name found

Fuel: Electric/gas **Temperature Differential Heat Mode: Defective**

Condition: Items:

Defective Heat Operation: Unit did not turn on. All switches appeared on.

NI A/C System The A/C system should not be turned on until it has been higher than

> 65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional **Condensate Removal:** PVC to pump to hose. **Functional** Thermostat: Old cad area hallway

Flue Pipe: Metal **Functional Functional** Flue Lines: Metal Functional Filter: Clean

Guard Shack

Location Label Roof: NA Approximate Age: 10 years **Location Label Thermostat:** On unit Capacity: Approx. 1 ton cooling. PTAC

Type: **Temperature Differential Cooling:** NΙ **Fuel:** Electric **Temperature Differential Heat Mode:** 20F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat. NI


The A/C system should not be turned on until it has been higher than A/C System

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: Within unit. **Functional** On unit Thermostat: NP Flue Pipe: NΡ NP Flue Lines: NP

NP NP. This is typical for this type. Filter:

Cover off outside coils. Conditional Misc.:



NI

File: SampleIndustrialInspectionReport Page 22 of 70 Client: Client

December 10, 2012

Lab Area First Floor

Location Label Outside: P6 Approximate Age: 15 years

Location Label Thermostat: Not labeled Capacity: 25 ton

Manufacturer:TraneTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:10F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: Drain outside.
Functional Thermostat: Main lab area

Functional Flue Pipe: Metal
Functional Flue Lines: Metal

Defective Filter: No filter found.

Lab Area heating test area chiller

Location Label outside: NP Approximate Age: 15 years

Location Label Thermostat: 4 systems Capacity: chiller

Manufacturer:No name foundTemperature Differential Cooling:NIFuel:ElectricTemperature Differential Heat Mode:NP

Condition: Items:

NP Heat Operation: NP

NI A/C System This chill water system disconnect was turned off, and hopefully drained

to prevent freezing.

Functional Condensate Removal: NP

Functional Thermostat: 4 test rooms

Functional Flue Pipe: NP Functional Flue Lines: NP Functional Filter: NP

Page 23 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Lab area 10 ton unit

Location Label outside: Not labeled Approximate Age: 15 years

Location Label Thermostat: Not found Capacity: 10 ton

Manufacturer: American Standard **Temperature Differential Cooling:** NI **Fuel:** Electric/? **Temperature Differential Heat Mode:** NI

Condition: Items:

NI **Heat Operation:** NI, System not located inside.

NI A/C System The A/C system should not be turned on until it has been higher than

> 65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

NI **Condensate Removal:** NI NI Thermostat: NI Flue Pipe: ΝI NΙ NI Flue Lines: NI NI Filter: NI

Engineering Area, 2nd Floor Main area

Location Label Outside: Likely G6 Approximate Age: 15 years **Location Label Thermostat:** Capacity: 5 ton cooling Not labeled

Manufacturer: Trane **Temperature Differential Cooling:** NI Electric/gas **Temperature Differential Heat Mode:** 10F Fuel:

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat. NI

The A/C system should not be turned on until it has been higher than A/C System

> 65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

PVC to outside. **Functional Condensate Removal:**

Middle engineering area **Functional** Thermostat:

Functional Flue Pipe: Metal **Functional** Flue Lines: Metal Functional Filter: Clean

Page 24 of 70 File: SampleIndustrialInspectionReport Client: Client

December 10, 2012

Engineering Area, 2nd Floor right rear

Location Label Outside:E6Approximate Age:15 yearsLocation Label Thermostat:E6Capacity: 3 ton cooling

Manufacturer:TraneTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:19F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

Functional Thermostat: Right rear engineering area

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Clean

Engineering Area, 2nd Floor right front

Location Label Outside: D6 Approximate Age: 15 years
Location Label Thermostat: D6 Capacity: 3 ton cooling

Manufacturer:TraneTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:10F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

Functional Thermostat: 2nd floor, right front main area

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Clean

Page 25 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Engineering Area, 2nd Floor conference room front side

Location Label Outside: Κ Approximate Age: 15 years **Location Label Thermostat:** K6 Capacity: 3 ton cooling

Temperature Differential Cooling: NΙ Manufacturer: Trane **Fuel:** Electric/gas **Temperature Differential Heat Mode:** 10F

Condition: Items:

Functional **Heat Operation:** Adequate. This unit could maintain normal setpoints of the thermostat. NI

A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Conditional **Condensate Removal:** PVC to drain. Leak apparent. Ceiling in pieces below drain.

Functional Thermostat: 2nd floor conference room front side

Functional Flue Pipe: Metal **Functional** Flue Lines: Metal Functional Filter: Clean



Engineering Area, 2nd Floor conference room rear side

Location Label Outside: J6 or L6 Approximate Age: 15 years

Location Label Thermostat: J6, two labeled this Capacity: 3 ton cooling

Manufacturer: Trane **Temperature Differential Cooling:** NΙ Electric/gas **Temperature Differential Heat Mode:** 22F Fuel:

Condition: Items:

Functional Adequate. This unit could maintain normal setpoints of the thermostat. **Heat Operation:**

The A/C system should not be turned on until it has been higher than NI A/C System

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

Functional 2nd floor conference room rear side. Thermostat:

Functional Flue Pipe: Metal **Functional** Flue Lines: Metal

Filter: Not found. Likely inside push locked doorknob office. NI

Page 26 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Engineering Area, 1st Floor conference room left side

Location Label Outside: J6 or L6 Approximate Age: 15 years

Location Label Thermostat: J6. two labeled this Capacity: 3 ton cooling

Temperature Differential Cooling: Manufacturer: Trane NΙ **Fuel:** Electric/gas **Temperature Differential Heat Mode:** 10F

Condition: Items:

Functional **Heat Operation:** Adequate. This unit could maintain normal setpoints of the thermostat. NI

A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional **Condensate Removal:** PVC to drain.

Functional Thermostat: 1st floor conference room left side

Flue Pipe: Metal **Functional Functional** Flue Lines: Metal Functional Filter: Clean

Engineering Area, 1st Floor conference room right side

Location Label Outside: H6 Approximate Age: 15 years **Location Label Thermostat:** H6 Capacity: 3 ton cooling

Manufacturer: Trane **Temperature Differential Cooling:** NΙ Electric/gas **Temperature Differential Heat Mode:** 20F Fuel:

Condition: Items:

Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat. Functional

The A/C system should not be turned on until it has been higher than NI A/C System

> 65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

1st floor conference room right side Functional Thermostat:

Functional Flue Pipe: Metal **Functional** Flue Lines: Metal **Functional** Filter: Clean

Page 27 of 70 File: SampleIndustrialInspectionReport Client: Client

December 10, 2012

Engineering Area, 1st Floor by elevator

Location Label Outside: Approximate Age: 15 years **Location Label Thermostat:** 16 Capacity: 3 ton cooling

Temperature Differential Cooling: NΙ Manufacturer: Trane **Fuel:** Electric/gas **Temperature Differential Heat Mode:** 27F

Condition: Items:

Functional **Heat Operation:** Adequate. This unit could maintain normal setpoints of the thermostat. NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional **Condensate Removal:** PVC to drain. **Functional** Thermostat: 1st floor by elevator

Flue Pipe: Metal **Functional Functional** Flue Lines: Metal Functional Filter: Clean

Engineering Area, 1st Floor right side

Location Label Outside: F6 Approximate Age: 15 years **Location Label Thermostat:** F6 Capacity: 5 ton cooling

Temperature Differential Cooling: Manufacturer: Trane NI **Temperature Differential Heat Mode:** Fuel: Electric/gas 20F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat. NI

A/C System The A/C system should not be turned on until it has been higher than

> 65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional PVC to drain. **Condensate Removal:** Functional Thermostat: 1st floor right side

Metal **Functional** Flue Pipe: Flue Lines: Metal Functional Functional Filter: Clean

Page 28 of 70 File: SampleIndustrialInspectionReport Client: Client

December 10, 2012

Engineering Area

Location Label Outside:C6Approximate Age:15 yearLocation Label Thermostat:Not foundCapacity: 3 ton cooling

Manufacturer: Trane Temperature Differential Cooling: NI Fuel: Electric/gas Temperature Differential Heat Mode: NI

Condition: Items:

NI Heat Operation: NI

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

NI Condensate Removal: NI

NI Thermostat: Not located.

NI Flue Pipe: NI
NI Flue Lines: NI
NI Filter: NI

Old lab area

Location Label Roof:Not labeledApproximate Age:25 yearsLocation Label Thermostat:5ACapacity: 2 1/2 ton cooling

Manufacturer: Carrier Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: 20F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated. Functional Condensate Removal: Drain to roof.

Functional Thermostat: Front Office
Functional Flue Pipe: Metal
Functional Flue Lines: Metal

Functional Filter: Clean

Page 29 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Old lab area

Location Label Roof: 5B Approximate Age: 32 years

Location Label Thermostat: 5B Capacity: 15 ton

Manufacturer: York Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: 18F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: Drain to roof.

Functional Thermostat: Large unfinished area

Functional Flue Pipe: Metal Functional Flue Lines: Metal

NI Filter: May be on roof.

Engineering 1st floor unfinished area

Location Label Outside: Not labeled Approximate Age: 15 years

Location Label Thermostat: Not labeled Capacity: NI

Manufacturer: Not determined Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: Defective

Condition: Items:

Defective Heat Operation: Defective or turned off.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

Functional Thermostat: Unfinished test area, outdoor gas lab.

Functional Flue Pipe: Metal Functional Flue Lines: Metal

Conditional Filter: Filter too hard to get to ever change.

Page 30 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Old lab

Location Label Roof: Not determined Approximate Age: 20 years
Location Label Thermostat: K2 Capacity: Not determined

Manufacturer: No name found Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: Defective

Condition: Items:

Defective Heat Operation: Defective or turned off. Damper not operational.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

Functional Thermostat: Old lab Functional Flue Pipe: Metal Functional Flue Lines: Metal

NI Filter: Rooftop likely

Old office, cad room

Location Label Roof: May be C5 Approximate Age: 25 years Location Label Thermostat: Not labeled. Capacity: If C5, 10 ton.

Manufacturer:FraserxxxxxxTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:40F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

Functional Thermostat: Old office cad room.

Functional Flue Pipe: Metal Functional Flue Lines: Metal

NI Filter: Likely rooftop.

Defective Misc.: Covers off of rooftop unit.



Page 31 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Old office, personnel

Location Label Roof: 2C Approximate Age: 20 years

Location Label Thermostat: 2C Capacity: 3 ton

Manufacturer:YorkTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:20F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.

Functional Thermostat: Personnel area of old office area

Functional Flue Pipe: Metal
Functional Flue Lines: Metal
Functional Filter: Adequate

Old Office Area

Location Label Roof:Not determinedApproximate Age:15 yearsLocation Label Thermostat:Not labeledCapacity:Not determined

Manufacturer: Not determined Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: Defective

Condition: Items:

Defective Heat Operation: Did not turn on.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Old office area, front left corner office

NI Flue Pipe: NI
NI Flue Lines: NI
NI Filter: NI

Page 32 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Old Office Area

Location Label Roof:2DApproximate Age:20 yearsLocation Label Thermostat:2DCapacity: 10 ton cooling

Manufacturer: York Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: 20F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Old office general area

Functional Flue Pipe: Metal Functional Flue Lines: Metal NI Filter: NI

Old Office Area

Location Label Roof: 2E Approximate Age: 5 years
Location Label Thermostat: 2E Capacity: 5 ton cooling

Manufacturer: York Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: Defective

Condition: Items:

Defective Heat Operation: Unit did not produce any heat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Old office general area, front middle

Functional Flue Pipe: Metal Functional Flue Lines: Metal NI Filter: NI

All units with fins facing the rear will have hail damage. Approximately 1/2 of all units on this

Page 33 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Old Office Area

Location Label Roof: Not determined Approximate Age: 20 years
Location Label Thermostat: No label Capacity: Not determined

Manufacturer: Not determined Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: Defective

Condition: Items:

Defective Heat Operation: Unit did not produce any heat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Old office computer system room.

Functional Flue Pipe: Metal Functional Flue Lines: Metal

NI Filter: Likely on roof

Old Office Area

Location Label Roof:G2Approximate Age:20 yearsLocation Label Thermostat:G2Capacity: 4 ton cooling

Manufacturer:BryantTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:12F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Old office general area

Functional Flue Pipe: Metal
Functional Flue Lines: Metal
Defective Filter: Missing

Old Office/HR Area

Conditional Roof units: K2 Bryant, 10 ton, covers off of unit.

L Trane, 5 ton, 9/88. M GE, 2.5 ton, 11/83.

These three systems on the roof appear to not have associated thermostats or

areas that need HVAC.

Page 34 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Front Door Foyer Area

Location Label Roof: 2A Approximate Age: 20 years
Location Label Thermostat: 2A Capacity: Approx. 3 ton

Manufacturer: York Temperature Differential Cooling: NI Fuel: Electric/gas Temperature Differential Heat Mode: 44F

Condition: Items:

NI

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

This unit is zone damper controlled with the next 3 systems.

All 4 should be set to the same temperature setpoint. This is Zone 3 of 4.

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Front door first glass wall area

Functional Flue Pipe: Metal Functional Flue Lines: Metal NI Filter: NI

Front Door Foyer Area

Location Label Roof:Not determinedApproximate Age:20 yearsLocation Label Thermostat:Not labeledCapacity: Approx. 3 ton

Manufacturer: Not determined Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: 40F

Likely this is unit 2B, 2F, or 2I.

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

This unit is zone damper controlled with the prior and next 2 systems.

All 4 should be set to the same temperature setpoint. This is Zone 2 of 4.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Front door reception clerk area

Functional Flue Pipe: Metal Functional Flue Lines: Metal NI Filter: NI

•

Page 35 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Front Door Foyer Area

Location Label Roof:Not determinedApproximate Age:20 yearsLocation Label Thermostat:Not labeledCapacity: Approx. 3 ton

Manufacturer:Not determinedTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:30F

Likely this is unit 2B, 2F, or 2I.

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

This unit is zone damper controlled with the prior and next 2 systems.

All 4 should be set to the same temperature setpoint. This is Zone 4 of 4.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Front door front door area

Functional Flue Pipe: Metal Functional Flue Lines: Metal NI Filter: NI

Front Door Foyer Area

Location Label Roof: Not determined Approximate Age: 20 years Location Label Thermostat: Not labeled Capacity: Approx. 3 ton

Manufacturer: Not determined Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: 30F

Likely this is unit 2B, 2F, or 2I.

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

This unit is zone damper controlled with the prior and next 2 systems. All 4 should be set to the same temperature setpoint. This is Zone 1 of 4.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

NI Condensate Removal: NI

Functional Thermostat: Front foyer, rear glassed in area

Functional Flue Pipe: Metal Functional Flue Lines: Metal NI Filter: NI

Page 36 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

HR Area

Location Label Roof: Not determined Approximate Age: 25 years
Location Label Thermostat: Not labeled Capacity: Not determined

Manufacturer:Not determinedTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:15F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to drain.
Functional Thermostat: Large HR area

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Adequate

Conditional Ducting: Air vent under Bike 2200-2299 is not connected to ductwork, in the middle

of the HR large room.

HR Area

Location Label Roof: J2 Approximate Age: 14 years
Location Label Thermostat: J2 Capacity: 10 ton cooling

Manufacturer:BryantTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:15F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Conditional Condensate Removal: No drain line is installed.

Functional Thermostat: HR access to plant personnel room.

Functional Flue Pipe: Metal
Functional Flue Lines: Metal
NI Filter: NI



Page 37 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Sales Area

Location Label Roof: G or 1H Approximate Age: 20 years
Location Label Thermostat: G1 Capacity: 5 ton cooling

Manufacturer:GoodmanTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:12F

It makes more sense with the pattern, if this unit was 1H, not G1. Another

Thermostat is also labeled G1.

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to outside.

Functional Thermostat: Sales area left side offices

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Adequate.

Sales Area

Location Label Roof: B Approximate Age: 20 years
Location Label Thermostat: B1 Capacity: 5 ton cooling

Manufacturer: Not found Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: 31F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to outside.

Functional Thermostat: Sales area front right.

Functional Flue Pipe: Metal
Functional Flue Lines: Metal
Functional Filter: Adequate.

Page 38 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Sales Area

Location Label Roof: 1A Approximate Age: 20 years **Location Label Thermostat:** Α1 Capacity: 5 ton cooling

Temperature Differential Cooling: NΙ Manufacturer: Not found **Fuel:** Electric/gas **Temperature Differential Heat Mode:** 25F

Condition: Items:

Functional **Heat Operation:** Adequate. This unit could maintain normal setpoints of the thermostat. NI

The A/C system should not be turned on until it has been higher than A/C System

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to outside.

Functional Sales area front middle. Thermostat:

Functional Flue Pipe: Metal Functional **Flue Lines:** Metal **Functional** Filter: Adequate

Sales Area

Location Label Roof: D Approximate Age: 20 years **Location Label Thermostat:** D1 Capacity: 5 ton cooling

Manufacturer: Not found **Temperature Differential Cooling:** NI **Temperature Differential Heat Mode:** Electric/gas **Defective** Fuel:

Condition: Items:

Defective Covers off of the heater manifold is keeping the unit from turning on. **Heat Operation:** NI

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Functional **Condensate Removal:** PVC to outside. Sales area front left. Functional Thermostat:

Functional Flue Pipe: Metal **Functional Flue Lines:** Metal

Filter housing loose. Conditional Filter:

Page 39 of 70 File: SampleIndustrialInspectionReport Client: Client

December 10, 2012

Sales Area

Location Label Roof: 1C Approximate Age: 20 years **Location Label Thermostat:** C₁ Capacity: 5 ton cooling

Temperature Differential Cooling: NI Manufacturer: Heil **Fuel:** Electric/gas **Temperature Differential Heat Mode: Defective**

Condition: Items:

Defective Covers off of the heater manifold is keeping the unit from turning on. **Heat Operation:** The A/C system should not be turned on until it has been higher than NI A/C System

> 65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional PVC to outside. **Condensate Removal:**

Functional Thermostat: Sales area front left corner office.

Functional Flue Pipe: Metal **Flue Lines:** Metal Functional

Conditional Filter: Filter housing loose.



Sales Area

G **Location Label Roof:** Approximate Age: 10 years Capacity: 5 ton cooling **Location Label Thermostat:** G1

Manufacturer: Goodman **Temperature Differential Cooling:** NI **Fuel:** Electric/gas **Temperature Differential Heat Mode:** 15F

Condition: Items:

Functional **Heat Operation:** Adequate. This unit could maintain normal setpoints of the thermostat. NI

A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional **Condensate Removal:** PVC to outside. Sales area rear left. **Functional** Thermostat:

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Adequate

Conditional Misc.: Disconnect not mounted upright

or secured, but labeled vertically.



Page 40 of 70 File: SampleIndustrialInspectionReport Client: Client

December 10, 2012

Sales Area

Location Label Roof: 1E Approximate Age: 20 years E1 Capacity: 5 ton cooling **Location Label Thermostat:**

Temperature Differential Cooling: NΙ Manufacturer: Goodman **Fuel:** Electric/gas **Temperature Differential Heat Mode:** 15F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat. NI

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to outside.

Functional Sales area rear middle left. Thermostat:

Functional Flue Pipe: Metal Functional **Flue Lines:** Metal **Functional** Filter: Adequate

Sales Area

Location Label Roof: Approximate Age: 20 years **Location Label Thermostat:** Not labeled Capacity: 5 ton cooling

Manufacturer: Goodman **Temperature Differential Cooling:** NΙ **Fuel:** Electric/gas **Temperature Differential Heat Mode:** 15F

This unit is likely system I1, with the others accounted for and likely the

one labeled G1 for the right side offices really being System H1.

Condition: Items:

Functional **Heat Operation:** Adequate. This unit could maintain normal setpoints of the thermostat. NI

A/C System The A/C system should not be turned on until it has been higher than

> 65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Condensate Removal: Functional PVC to outside.

Functional Thermostat: Sales area rear middle right.

Functional Flue Pipe: Metal Functional **Flue Lines:** Metal Functional Filter: Adequate

Page 41 of 70 File: SampleIndustrialInspectionReport Client: Client

December 10, 2012

Sales Area

Location Label Roof:FApproximate Age:20 yearsLocation Label Thermostat:FCapacity:1.5 ton cooling

Manufacturer:GoodmanTemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:19F

Condition: Items:

Functional Heat Operation: Adequate. This unit could maintain normal setpoints of the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to outside.

Functional Thermostat: Sales conference Room.

Functional Flue Pipe: Metal Functional Flue Lines: Metal Functional Filter: Adequate

Sales Area

Location Label Roof: 1J Approximate Age: 20 years
Location Label Thermostat: J1 Capacity: 2 ton cooling

Manufacturer: Bryant Temperature Differential Cooling: NI
Fuel: Electric/gas Temperature Differential Heat Mode: Defective

Condition: Items:

Defective Heat Operation: No power was on the thermostat.

NI A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to outside.
Functional Thermostat: Sales left rear office.

Functional Flue Pipe: Metal Functional Flue Lines: Metal NI Filter: NI

Page 42 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Sales Area

Location Label Roof: NA Approximate Age: NI

Location Label Thermostat: Window AC Capacity: NI

Manufacturer:NITemperature Differential Cooling:NIFuel:ElectricTemperature Differential Heat Mode:NI

Condition: Items:

NI Heat Operation: NI

Defective A/C System This unit is not installed in a manner to function correctly.

The back side of this unit is not to outdoors.

Defective Condensate Removal: Pan not connected to PVC drain. Caused floor of room for HVAC units


1E, 1F, 1G, 1I, and 1H to be soaked, and water drained to conference


room.

Functional Thermostat: Utility room off of Sales conference room

Functional Flue Pipe: Metal Functional Flue Lines: Metal NI Filter: NI

This unit is not installed in a manner to function correctly.





1E, 1F, 1G, 1I, and 1H to be soaked, and water drained to conference room.





Page 43 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Paint Area

Location Label Outside: Not labeled Approximate Age: 5 years
Location Label Thermostat: Not found Capacity: Approx. 5 ton cooling

Manufacturer:NITemperature Differential Cooling:NIFuel:Electric/gasTemperature Differential Heat Mode:19F

Condition: Items:

NI Heat Operation: I could not find the thermostat for the unit on the stand in the picture below.

NI A/C System The A/C system should not be turned on until it has been higher than

A/C System The A/C system should not be turned on until it has been higher than 65F for 24 hours. This should be checked for 15-20F differential

between the supply and return registers when it can be operated.

Functional Condensate Removal: PVC to outside.

NI Thermostat: NI
Functional Flue Pipe: Metal
Functional Flue Lines: Metal
NI Filter: NI

Conditional Misc.: The York unit on the pad is disconnected from power.



Page 44 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Warehouse Heaters

Condition: Location:

Rear warehouse:

Back row:

DefectiveLeftmost:Fan only, no heat.Defective2nd from left:Would not turn on.

Functional **3rd from left:** Adequate.

DefectiveMiddle:Thermostat missing.Defective2nd from right:Would not turn on.

Functional Rightmost: Adequate.

Middle row:

Functional **Leftmost:** Adequate.

Defective Just left of center: Would not turn on. Center, front: Fan only, no heat.

Defective Center, rear: One of two fans turned on, no heat.

Functional **Rightmost:** Adequate.

Front row:

Functional **Leftmost:** Adequate.

Defective2nd from left:Thermostat missing.Defective2nd from right:Would not turn on.DefectiveRightmost:Would not turn on.

Front warehouse:

Conditional Front middle left: Could not locate the thermostats to turn this heater on.

Conditional Front middle right: Could not locate the thermostats to turn this heater on.

Functional Large left side unit: Adequate.

Page 45 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Plumbing

Visible water supply lines. Visible waste/soil and vent lines. Fixtures and faucets. Domestic hot water system and fuel source. Describe the material of the main line and water supply lines. Verify the presence of a main water supply valve. Describe the type of sanitary waste piping. Describe the type and capacity of domestic water heating unit(s). Inspect the condition of accessible and visible water and waste lines. Inspect and operate fixtures and faucets. Inspect and operate the domestic hot water systems. Inspect and operate drain pumps and waste ejector pumps when possible. Test the water supply for functional flow. Test waste lines from sinks, tubs and showers for functional drainage.

General

Items:

Functional Water Lines: Mostly Copper

Defective Vent Pipes: Cast/PVC. Pipe broke in two at the front left column of the front

warehouse. This is about a 5 inch cast pipe broken in two.

I failed to take a picture of this.

Functional **Drain Pipes:** Cast/PVC

Defective Gas lines: A hose ran in the rafters near the left wall of the warehouse.

This appears to be on and from a gas line.



Page 46 of 70

Client: Client File: SampleIndustrialInspectionReport

Interior Rooms

Observe the visible condition of the surfaces of walls, ceilings, and floors relative to structural integrity and evidence of water penetration. Verify the presence of steps, stairways, balconies, handrails and guardrails and observe their condition. Describe type, material, condition and operation of a representative number of windows, doors and their hardware. Inspect the condition of the public and office areas. Inspect the condition of the private areas. Locate and observe a representative number of electrical outlets/fixtures and wiring in each room. Comment on presence or absence of smoke detectors. Observe condition and operation of plumbing fixtures and components in each room.

Rear warehouse break area - Men's Bath

Condition: Items:

Functional Ceiling: Metal

Functional Walls: Concrete block Functional Floor: Coated concrete

Functional Doors: Metal
Functional Sink/Basin: Ceramic
Functional Faucets/Traps: Metal

Defective Toilet:4 Ceramic. 2nd from left taped up. Did not test. **Defective**Urinal:
3 Ceramic. Drain leaking, center and right urinals.

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.



Rear warehouse break area - Women's Bath

Condition: Items:

Functional Ceiling: Metal

Functional Walls: Concrete block Functional Floor: Coated concrete

Functional Doors: Metal Functional Sink/Basin: Ceramic Functional Faucets/Traps: Metal

Defective Toilet:5 Ceramic, 2nd and 4th ones loose from floor.

NP Urinal: NP

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Defective Electrical: Blower removed with bare wires

that were likely still powered.



Water Heater

Manufacturer: Promax **Location:** Rear warehouse break area.

Fuel: Electric

Condition: Items:

Conditional State Inspection: No inspection sticker found.

Functional Operation: Not on.
NP Flue Pipe: NP
Functional TPRV and Drain Tube:: To floor

Functional Capacity: 50 gallon

Page 47 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Front warehouse raised office area - Men's Bath

Condition: Items: Functional Ceiling: Suspended ceiling Functional Walls: Drywall/paint Functional Floor: Vinyl tile **Functional** Wood Doors: Metal Functional Sink/Basin:

Defective Faucets/Traps: Metal/PVC. Water appears off from this area. Drain in floor stinking badly.

DefectiveToilet:

1 Ceramic closed from use. Did not test.

NP Urinal: NP

Functional HVAC Source: Central air vent NP Ventilation: None present.

Front warehouse raised office area - Women's Bath

Condition: Items: Functional Ceiling: Suspended ceiling Functional Walls: Drywall/paint Functional Floor: Vinyl tile Wood Functional Doors: **Functional** Metal Sink/Basin: Functional Faucets/Traps: Metal/PVC.

Defective Toilet:2 Ceramic. Water appears turned off for this area. Could not test.

NP Urinal: NP

Functional HVAC Source: Central air vent NP Ventilation: None present.

Page 48 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Front warehouse break area - Men's Bath

Condition: Items:

Functional Ceiling: Drywall/paint Functional Walls: Concrete block

Functional Floor: Tile
Functional Doors: Metal
Functional Sink/Basin: 2 Ceramic
Functional Faucets/Traps: Metal

Defective3 Ceramic. Rear loose and leaking, middle too full to test, front very loose and

leaking.

Defective Urinal: 2 Ceramic. Rear one leaking supply plumbing when flush.

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Front warehouse break area - Women's Bath

Condition: Items:

Functional Ceiling: Drywall/paint Functional Walls: Concrete block

FunctionalFloor:TileFunctionalDoors:MetalFunctionalSink/Basin:2 CeramicFunctionalFaucets/Traps:Metal

Defective Toilet: 4 Ceramic. Rear loose, front leaking.

NP Urinal: NP

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Front warehouse break area - Water Heater

Manufacturer: A.O.smith Location: Front warehouse closet

Fuel: Electric

Condition: Items:

Functional State Inspection: Inspection 12/1/94

Defective Operation: Not on. Leaking feed water plumbing.

NP Flue Pipe: NP

Functional TPRV and Drain Tube:: To floor

Functional Capacity: 76.8 gallon

DefectiveCirculation Pump:Not functioning.ConditionalSink in this area:Cold water had no flow.



Page 49 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Engineering 2nd floor - Men's Bath

Condition:Items:FunctionalCeiling:Suspended CeilingFunctionalWalls:Drywall/paint

Functional Floor: Tile
Functional Doors: Wood
Functional Sink/Basin: 2 Steel

Conditional Faucets/Traps: Metal. Cold handle does not stop at off.

Functional Toilet: 2 Ceramic.
Functional Urinal: 1 Ceramic.
Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Defective Lights: No lights.

Engineering 2nd floor - Women's Bath

Condition: Items:
Functional Ceiling: Suspended Ceiling

Functional Walls: Suspended Certain Suspended Ce

Functional Floor: Tile
Functional Doors: Wood
Functional Sink/Basin: 2 Steel

Conditional Faucets/Traps: Metal. Rear water faucet leaks.

Functional Toilet: 2 Ceramic.

NP Urinal: NP

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Conditional Lights: Most lights out.

Engineering 2nd floor - Water Heater

Manufacturer: Not found Location:

Fuel:

Condition: Items:

NI State Inspection:
NI Operation:
NI Flue Pipe:

NI TPRV and Drain Tube::

NI Capacity:

NI Circulation Pump: NI Sink in this area:

Page 50 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Engineering 1st floor - Men's Bath

Condition: Items:
Functional Ceiling: Suspended Ceiling. Some stains in the tiles.

Functional Walls: Drywall/paint

Functional Floor: Tile
Functional Doors: Wood
Functional Sink/Basin: 2 Steel
Functional Faucets/Traps: Metal.

Defective Toilet: 2 Ceramic. Water turned off.

Functional Urinal: 1 Ceramic.
Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Defective Lights: No lights.

Engineering 1st floor - Women's Bath

Condition: Items:

Functional Ceiling: Suspended Ceiling Functional Walls: Drywall/paint

Functional Floor: Tile
Functional Doors: Wood
Functional Sink/Basin: 2 Steel

Conditional Faucets/Traps: Metal. Rear water faucet leaks.

Defective Toilet: 2 Ceramic. Handicap toilet turned off.

NP Urinal: NP

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Conditional Lights: Most lights out.

Engineering 1st floor - Sink for break room

Condition: Items:

Defective Faucets/Traps: Leaking badly.
Conditional Sink/Basin: Leaking

Old lab - Sink

Condition: Items:

Functional Faucets/Traps: Metal/PVC Functional Sink/Basin: Stainless

Old Office - Office with personnel bath

Condition: Items:
Functional Ceiling: Suspended Ceiling.
Functional Walks Described

Functional Walls: Drywall/paint
Functional Floor: Carpet
Functional Doors: Wood
Functional Sink/Basin: 2 Steel

Functional Faucets/Traps: Metal. Instant how water not plugged in. Not tested.

Functional Toilet: Ceramic NP Urinal: NP

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Page 51 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Old Office - Men's Bath

Condition: Items: Functional Ceiling: Suspended Ceiling **Functional** Drywall/paint Walls: Functional Floor: Vinyl Tile **Functional** Wood Doors: 2 Steel Functional Sink/Basin: Functional Faucets/Traps: Metal.

Defective Toilet: 2 Ceramic. Left too full to test. **Defective Urinal:** Leaking badly when flush

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Old Office - Women's Bath

Condition: Items: **Functional** Ceiling: Suspended Ceiling Functional Walls: Drywall/paint **Functional** Floor: Vinyl Tile **Functional** Wood Doors: Functional Sink/Basin: 2 Steel

Conditional Metal. Rear water faucet leaks. Faucets/Traps: 3 Ceramic. Left water turned off. **Defective Toilet:**

NP **Urinal:** NP

Functional **HVAC Source:** Central air vent

Functional Ventilation: Yes.

Water Heater

Manufacturer: A.O.Smith Location: Old lab second floor

Fuel: Electric

Condition: Items:

Conditional State Inspection: No inspection sticker found.

Functional Operation: Not on. NP Flue Pipe: NP **Functional** TPRV and Drain Tube:: To floor Functional Capacity: Approximately 50 gallon

> Client: Client File: SampleIndustrialInspectionReport

Page 52 of 70

December 10, 2012

HR Office - Men's Bath

Condition:Items:FunctionalCeiling:Metal.FunctionalWalls:Drywall/paintFunctionalFloor:TileFunctionalDoors:Wood

Functional Sink/Basin: 1 piece molded

Functional Faucets/Traps: Metal. Functional Toilet: Ceramic.

Conditional Urinal: Leaking when flush
Functional **HVAC Source:** Central air vent

Functional Ventilation: Yes.

Defective Lights: No lights

HR Office - Women's Bath

Condition: Items: Functional Ceiling: Metal. Functional Walls: Drywall/paint **Functional** Floor: Tile **Functional** Doors: Wood Functional Sink/Basin: 1 piece molded

Functional Faucets/Traps: Metal.

Functional Toilet: Ceramic.

ConditionalUrinal:Leaking when flushFunctionalHVAC Source:Central air vent

Functional Ventilation: Yes.

Conditional Lights: Few lights

Page 53 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Sales Office - Men's Bath

Condition: Items: Functional Ceiling: Metal. **Functional** Drywall/paint Walls: **Functional** Floor: Tile **Functional** Doors: Wood Functional Sink/Basin: Formica Functional Faucets/Traps: Metal. **Functional Toilet:** 2 Ceramic. Functional **Urinal:** 1 Ceramic. **HVAC Source:** Central air vent Functional

Functional Ventilation: Yes.

Defective Electric The outlet is not GFCI protected.

Sales Office - Women's Bath

Condition: Items: **Functional** Ceiling: Metal. **Functional** Walls: Drywall/paint Tile **Functional** Floor: Wood **Functional** Doors: Formica Functional Sink/Basin: Functional Faucets/Traps: Metal. Functional **Toilet:** 3 Ceramic. NP NP **Urinal:**

Functional HVAC Source: Central air vent

Functional Ventilation: Yes.

Defective Electric The outlet is not GFCI protected.

Sales Office - Water Heater

Manufacturer: Rudd Location: Between Bath's above

Fuel: Gas

Condition: Items:

Conditional State Inspection: No inspection sticker found.

Functional Operation: Not on. Functional Flue Pipe: Metal

Defective TPRV and Drain Tube:: CPVC with taped joint. Drain tube is not installed in a safe manner.

Functional Capacity: Approximately 50 gallon

Sales Office - Sink

Condition: Items:

Defective Faucets/Traps: Metal/PVC. It appears the drain is leaking inside the wall behind the sink.

Moisture meter was pegged-over 44%.

Functional Sink/Basin: Fiberglass



Page 54 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Lab Area

Condition: Items:

Functional Ceiling: Building steel structure/Suspended tiles

Functional Walls: Metal.
Functional Floor: Concrete

Conditional Doors: Wood and metal doors. 2 of 3 wood office doorknobs broke.

Functional Windows: Fixed and tilting Conditional Lights: Many lights out.

Defective Exhausts: #2 Exhaust Fan has no controller. Did not work.



Engineering 2nd Floor

Condition: Items:

Conditional Ceiling: Suspended tiles. Several stained tiles.

Functional Walls: Drywall/paint.

Functional Floor: Carpet

Conditional Doors: Wood. Combo pushbutton door knob would not open.

Functional Windows: Sliding

Conditional Lights: Many lights out.

Engineering 1st Floor

Condition: Items:

Conditional Ceiling: Suspended tiles. Several stained tiles. Missing under former condensate leak.

Functional Walls: Drywall/paint.
Functional Floor: Carpet, some stains.

Functional Doors: Wood.
Functional Windows: Sliding

Conditional Lights: Many lights out.

Page 55 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Old Office Area

Condition: Items: Defective Ceiling:

Conditional Walls: Conditional

Floor:

Functional Doors:

Windows: Functional Conditional Lights:

Catch pan for leak.




Suspended tiles. Many stained, broken tiles. Stains were not active leaks. Drywall/paint. Dryerase board used as wallboard. Many damaged areas.

Carpet, many stains and worn areas.

Wood.

Fixed and sliding. Many lights out.







Condition: Items: **Defective**

Ceiling: Suspended tiles. Many stained, broken tiles. Walls: Drywall/paint. Many damaged areas.

Defective Floor: Carpet, many stains and worn areas. Active roof leak in sink area damaging

tiles.

Functional Functional

Conditional

Conditional

Wood. Doors: Fixed and sliding. Windows: Lights: Many lights out.



Sales Area

Condition: Items: Conditional

Ceiling: Suspended tiles. Some stained tiles.

Functional Walls: Drywall/paint.

Conditional Carpet. Wet area in conference room. Floor:

Functional Doors: Wood.

Functional Fixed and sliding. Windows: Functional Lights: A few lights out.







Client: Client Page 56 of 70 File: SampleIndustrialInspectionReport

December 10, 2012

Front Warehouse Break room, Office area.

Condition: Items:

DefectiveCeiling:Suspended tiles. Many stained tiles.FunctionalWalls:Drywall/paint, concrete block.

Conditional Floor: Vinyl tile. Concrete under tile swelling under and near coke machine.

Functional **Doors:** Wood. Functional **Windows:** Fixed.

Defective Lights: Many lights out.



Front Warehouse Second Floor office area.

Condition: Items:

Defective Ceiling: Suspended tiles. Many stained tiles.

Functional Walls: Drywall/paint.
Functional Floor: Vinyl tile
Functional Doors: Wood.
Functional Windows: Fixed.

Defective Lights: Many lights out.

Defective Exit Doors: Several doors chained shut. Left side

warehouse exit door break-in damage.



Rear Warehouse Office Break area.

Condition: Items:
Functional Ceiling: Metal

Functional Walls: Metal

Functional Floor: Concrete, Surfaced concrete.

Functional **Doors:** Metal Functional **Windows:** Fixed.

Defective Lights: Many lights out.

Page 57 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Accessories

Misc. Equipment

Condition: Items:

Defective Overhead Doors: Bright orange

Defective Overhead Doors: Bright orange door on right wall of first warehouse did not operate.

Defective Did not function.

Defective Fire Extinguishers: I would guess about 10% at the most are all the fire extinguishers that

are installed. No extinguishers had an inspection date more recent

than 2010.

Elevator

Condition: Items: Functional **State Inspection:** Not found Functional Visible condition: Adequate. Functional **Brand:** Dover Elevators. Model: EP7025 Functional Functional **Exhaust:** Adequate.

Page 58 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Fire Alarm System at Riser #1

Condition: Items:

Defective Inspection last performed No Inspection sticker found.

Defective Insufficiencies corrected Several insufficiencies exist. Bypassed input 16. Flow Switch.

Defective Monitoring Service Provider: NP

Defective Condition of equipment Disconnected from power and from backup battery.


NI **Any current alarms** Not in service.

Functional Brand: Fire Control Instruments
Functional Model: 7200 Fire Alarm Panel

Conditional Devices: Smoke alarms, hand pull stations, flow detectors, valve position

devices, horns, elevator failure, gas cutoff. Status of all of these inputs are unknown.

Bypassed input 16. Flow Switch.



Disconnected from power and from backup battery.



Fire Alarm System at Front Right wall of Front Warehouse

Condition: Items:

Defective Inspection last performed No Inspection sticker found.

Functional Insufficiencies corrected None noted.
Functional Monitoring Service Provider: Sentry Net

Functional Condition of equipment Appears adequate for this area of the plant.

Functional Any current alarms None present.
Functional Brand: Fire Lite
Functional Model: MS5UD

Page 59 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Sprinkler System

Condition: Items: **Functional** Company performing inspection Eagle Fire **Inspection last performed:** Functional Riser #1: 1/4/2012 **Conditional** Riser #2: 1/4/2010. This date was listed after 5/13/10, so likely should be 1/4/12. No spare sprinkler heads. Labels painted.

Conditional Riser #3: 1/4/2012 No spare sprinkler heads. Conditional Riser #4: 1/4/2012 No spare sprinkler heads.

Conditional Riser #5: 1/4/2012 No spare sprinkler heads.

Defective Installed April 1992. No inspection dates found from then. Riser Sales Area:

Conditional Any areas valved incorrectly All active risers were opened and pressurized.

> One inactive riser was still pressurized with no valves to drain/flush this riser and header on a regular basis, next to #3.

Gauges last replaced:

Functional Riser #1: 2009 Riser #2: 2009 Functional Riser #3: 2009 Functional Riser #4: 2009 Functional Riser #5: 2009 Functional

Defective Riser Sales Area: Installed April 1992. No dates were found on the gauges. **Defective Tone Bells:** Riser at Sales Area outside Tone Bell covered with tape

for painting.

Open.

One inactive riser was still pressurized with no valves to

drain/flush this riser and header on a regular basis.



No spare sprinkler heads.









Page 60 of 70 File: SampleIndustrialInspectionReport Client: Client

December 10, 2012

- 2. GENERAL LIMITATIONS AND EXCLUSIONS
- 2.1 Inspections performed under the Standards exclude any item(s) concealed or not readily accessible to the inspector. The inspector is not required to move furniture, personal, or stored items; lift floor coverings; move attached wall, ceiling coverings, or panels; or perform any test(s) or procedures(s) which could damage or destroy the item(s) being evaluated.
- 2.2 The following are excluded and not limited to: appliances, recreational facilities, alarms, intercoms, speaker systems, radio controlled devices, security devices and lawn irrigation systems.
- 2.3 The determination of the presence of or damage caused by termites or any other wood-damaging insects or organism is excluded.
- 2.4 Also excluded from a standard inspection is the determination of the indoor air quality or sickness of any building including, but not limited to, the presence or absence of all manner of biological activity, such as molds, insects, birds, pets, mammals, and other flora and fauna, and their consequent physical damage, toxicity, odors, waste products, and noxiousness.
- 2.5 Use of special instruments or testing devices, such as amp meters, pressure gauges, moisture meters, gas detectors and similar equipment is not required.
- 2.6 The inspection is not required to include information from any source concerning previous property, geological, environmental or hazardous waste conditions, manufacturer recalls or conformance of proper manufacturer's installation of any component or system, or information contained in Consumer Protection Bulletin. The inspection is not required to include information from any source concerning past or present violations of codes, ordinances, or regulations.
- 2.7 The inspection and report are opinions only, based upon visual observation of existing conditions of the inspected property at the time of the inspection. THE REPORT IS NOT INTENDED TO BE, OR TO BE CONSTRUED AS, A GUARANTEE, WARRANTY, OR ANY FORM OF INSURANCE. The inspector will not be responsible for any repairs or replacements with regard to the property or the contents thereof.
- 2.8 The inspector is not required to determine property boundary lines or encroachments.
- 2.9 The inspector is not required to provide an inspection of any condominium common component, system or evaluate condominium reserve accounts.
- 2.10 The inspector is not required to enter any premises that visibly shows a physical threat to the safety of the inspector or others nor inspect any area or component that poses a danger to the inspector or others.

 The inspector is NOT required to:

- 3.3.1 Inspect fences or privacy walls.
- 3.3.2 Evaluate the condition of trees, shrubs, and or other vegetation.
- 3.3.3 Evaluate or determine soil or geological conditions, site engineering, or property boundaries.

The inspector is NOT required to:

- 4.3.1 Enter subfloor crawl spaces with headroom of less than 3 feet, obstructions, or other detrimental conditions.
- 4.3.2 Move stored items or debris or perform excavation to gain access.
- 4.3.3 Enter areas which, in the inspector's opinion, may contain conditions or materials hazardous to the health and safety of the inspector.
- 4.3.4 Operate sump pumps equipped with internal/water dependent switches.
- 5.3.1 Inspect buildings, decks, patios, retaining walls, and other structures detached from the structure.
- 5.3.2 Evaluate function of shutters, awnings, storm doors, storm windows and similar accessories.
- 5.3.3 Inspect or test the operation of security locks, devices, or systems.
- 5.3.4 Evaluate the presence, extent, and type of insulation and vapor barriers in the exterior walls.
- 5.3.5 Examine the interior of the flues or determine the presence or absence of flue liners.
- 5.3.6 Inspect for safety type glass or the integrity of thermal window seals or damaged glass.
- 6.3.1 Walk on or access a roof where it could damage the roof or roofing material or be unsafe for the inspector.
- 6.3.2 Remove snow, ice, debris or other conditions that prohibit the observation of the roof surfaces.
- 6.3.3 Inspect internal gutter and downspout systems and related underground drainage piping.
- 6.3.4 Inspect antennas, lightning arresters, or similar attachments.
- 6.3.5 Operate powered roof ventilators.
- 6.3.6 Determine remaining life expectancy of roof coverings, presence or absence of hail damage; manufacturers' defects, exceptions, installation methods or recalls; or number of layers.
- 6.3.7 Determine adequacy of roof ventilation.
- 7.3.1 Enter attic spaces with headroom of less than 5 feet, with insulation covering the ceiling joists, or bottom truss chord, or if there are obstructions, trusses, or other detrimental conditions.
- 7.3.2 Break or otherwise damage the surface finish or weather seal on or around access panels and covers.
- 8.3.1 Inspect or operate equipment housed in the utilities area except as otherwise addressed in the Standards.
- 8.3.2 Verify or certify safe operation of any auto reverse or related safety function(s) of a vehicle door.
- 9.3.1 Insert any tool, probe or testing device into the main or

Page 61 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

sub-panels.

- 9.3.2 Activate electrical systems or branch circuits which are not energized.
- 9.3.3 Operate overload protection devices.
- 9.3.4 Inspect ancillary systems, including but not limited to: burglar alarms, protection systems, low voltage relays, smoke/heat detectors, antennas, electrical de-icing tapes, lawn sprinkler wiring, swimming pool wiring, or any systems controlled by timers.
- 9.3.5 Move any objects, furniture, or appliances to gain access to any electrical component.
- 9.3.6 Test every switch, receptacle, and fixture.
- 9.3.7 Remove switch and outlet cover plates.
- 9.3.8 Inspect electrical equipment not readily accessible or dismantle any electrical device or control.
- 9.3.9 Verify continuity of connected service ground(s).
- 10.3.1 Operate any main, branch or fixture valve, except faucets, or determine water temperature.
- 10.3.2 Inspect any system that is shut-down or secured.
- 10.3.3 Inspect any plumbing components not readily accessible.
- 10.3.4 Inspect any exterior plumbing components or interior or exterior drain systems.
- 10.3.5 Inspect interior fire sprinkler systems.
- 10.3.6 Evaluate the potability of any water supply.
- 10.3.7 Inspect water conditioning equipment, including softener and filter systems.
- 10.3.8 Operate freestanding or built-in appliances.
- 10.3.9 Inspect private water supply systems.
- 10.3.10 Test shower pans, tub and shower surrounds, or enclosures for leakage.
- 10.3.11 Inspect gas supply system for materials, installation or leakage
- 10.3.12 Evaluate the condition and operation of water wells and related pressure tanks and pumps; the quality or quantity of water from on-site water supplies; or the condition and operation of on-site sewage disposal systems such as cesspools, septic tanks, drain fields, related underground piping, conduit, cisterns, and equipment
- 10.3.13 Inspect and operate fixtures and faucets if the flow end of the faucet is connected to an appliance.
- 10.3.14 Record location of any on-site visible fuel tanks within or directly adjacent to structure.
- 11.3.1 Activate or operate heating or other systems that do not respond to normal controls or have been shutdown.
- 11.3.2 To inspect or evaluate a heat exchanger.
- 11.3.3 Inspect equipment or remove covers or panels that are not readily accessible.
- 11.3.4 Dismantle any equipment, controls, or gauges.
- 11.3.5 Inspect the interior of flues.
- 11.3.6 Inspect heating system accessories, such as

- humidifiers, air purifiers, motorized dampers, heat reclaimers, etc.
- 11.3.7 Inspect solar heating systems.
- 11.3.8 Activate heating, heat pump systems, or other systems when ambient temperatures or other circumstances are not conducive to safe operation or may damage the equipment.
- 11.3.9 Evaluate the type of material contained in insulation and/or wrapping of pipes, ducts, jackets and boilers.
- 11.3.10 Operate digital-type thermostats or controls.
- 11.3.11 Evaluate the capacity, adequacy, or efficiency of a heating or cooling system.
- 11.3.12 Test or operate gas logs, built-in gas burning appliances, grills, stoves, space heaters, or solar heating devices.
- 11.3.13 Determine clearance to combustibles or adequacy of combustion air
- 12.3.1 Activate or operate cooling or other systems that have been shut-down.
- 12.3.2 Inspect gas-fired refrigeration systems, evaporative coolers, or wall or window-mounted air conditioning units.
- 12.3.3 Check the pressure of the system coolant or determine the presence of leakage.
- 12.3.4 Evaluate the capacity, efficiency, or adequacy of the system.
- 12.3.5 Operate equipment or systems if exterior temperature is below 60° Fahrenheit or when other circumstances are not conducive to safe operation or may damage the equipment.
- 12.3.6 Remove covers or panels that are not readily accessible.
- 12.3.7 Dismantle any equipment, controls, or gauges.
- 12.3.8 Check the electrical current drawn by the unit.
- 12.3.9 Operate digital-type thermostats or controls.

The inspector is NOT required to:

- 13.3.1 Ignite fires in a fireplace or stove to determine the adequacy of draft, perform a chimney smoke test, or inspect any solid fuel device in use.
- 13.3.2 Evaluate the installation or adequacy of inserts, wood burning stoves, or other modifications in a fireplace, stove, or chimney.
- 13.3.3 Determine clearance to combustibles in concealed areas
- 13.3.4 Determine cosmetic condition of ceilings, walls, floor coverings, and components.
- 13.3.5 Determine if the bath and/or kitchen vent fan ducting exhausts air to exterior of house.

Page 62 of 70 Client: Client File: SampleIndustrialInspectionReport

Conditional Item Summary

This report is issued for the sole use and benefit of the client(s) listed on page 2 of this report. It is valid only at the date and time of this inspection. An inspection does not reveal every problem that exists or ever could exist, but only those observed on the day of the inspection. Others after this date of the report may not and should not rely on the information in this report. Buyer should consult with a qualified contractor in the appropriate trade to determine the best repair methods, estimate costs, and perform any necessary repairs, servicing or maintenance discussed in this report or verbally at the time of the inspection prior to any final date as indicated in any Real Estate sales agreement. Since B and B Inspections does not dismantle equipment or perform invasive inspections or destructive testing, the contractors subsequent examinations may reveal additional required repairs. This summary is not the entire report. The complete report includes additional information of concern to the client. Pictures of Conditional, or Defective item are included in the report. The client must read the complete report to obtain all pertinent information. All suggested repairs should be performed by a qualified person.

Conditional ratings are defined as an item performing its intended function, but is in need of minor repair.

Defective ratings are defined as an item that appears to be sufficiently deficient; unsafe; hazardous or inoperative.

Surface drainage: Rear left corner has erosion. A drain tile has been installed to prevent further erosion.

Front ditch has a hole developing between drain grates.

These areas should be repaired.

Vegetation: Two areas on the left side have trees left in piles.

These areas should be cleaned up.

Lot: Evidence from all the construction

phases exist. Two rubble piles exist on the left side, one on rear side.

These areas should be cleaned up.

Outside Walks, steps: Some demolition areas not completed, right and left sides.

These areas should be completed.

Patio drainage: Left side demolition area has no smooth access to the

overhead door area. Does not drain.

This area should be completed and drainage supplied.

Retaining Wall: Corner near front door has loose and cracked bricks.

This area should be repaired before freezing causes further deterioration.

Fence: All fencing needs maintenance and repair. The one place where the

fence is next to the building structure, the fence is leaning. All other

areas are not contiguous with the structure.

These areas should be repaired.

Outside Covering: Metal siding. Left side near the inclined ramp damaged.

Left side rusting at bottom.

These areas should be repaired.

Trim/Fascia/Soffit: The fascia near between the HR and Sales areas sited earlier.

Above the gas meter at the engineering front wall soffit pieces

missing. Awning at left Sales door damaged.

These areas should be repaired.

Outside Doors: Some are chained shut that do not close securely.

These doors should be repaired.

Page 63 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Overhead Doors: Several bumpers missing, damaged, rear side.

These areas should be repaired.

Windows: Tilting window near fence left front was not closed.

This window should be repaired.

Patio: Right side missing standard steps.

Standard steps should be provided.

Gutters/downspouts: The gutters could easily gather debris to the right of the front door

and then water would leak into the office area.

The rear gutter on the rear warehouse had debris through most of the

length of the building.

The gutter between warehouses had debris on the left side.

The area to the right of the front door should be checked/cleaned on a very frequent basis. The warehouse gutters between the two warehouses and the rear warehouse gutter should be cleaned on a regular basis.

Soffit/fascia: The metal fascia bent between HR and Sales from a tree.

This area should be secured before blowing/falling causes more damage.

Roof Misc.: Cleanup of unused, unattached metal siding from recent repairs

was not done to the left of the front door.

These panels should be removed from the roof before blowing pieces causes damage.

Out of service equipment: On left middle side one transformer is not connected, and two

transformers have the fused knife switches disconnected.

These 3 transformers should be removed from the property.

Possible 5th service point: Near the left front corner of the property, a feed exists that

goes underground. I could not locate another main in the plant for

this feed. This pole likely feeds the transformer to the left

of HR offices.

This service should be determined if it is active, and panels inspected.

Breakers/Fuses: Shield missing on 2 breakers on the Rear Federal Pacific Main Panel.

These breakers should be repaired or replaced.

Labels: One breaker not labeled on the Rear Federal Pacific Main Panel.

This label should be determined and applied.

Labels: 3 of 5 breakers not labeled on the front Federal Pacific Main Panel.

These labels should be determined and applied.

Gas heater plumbing: Several offices connected, many not.

These individual office gas heaters should all be evaluated for operation and safety.

Guard shack PTAC cover: Cover off outside coils.

This should be installed.

Page 64 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

A/C System The A/C system should not be turned on until it has been higher than

65F for 24 hours. This should be checked for 15-20F differential between the supply and return registers when it can be operated.

All the AC units should be checked for operation when the temperatures allows this.

Condensate Removal: Assorted methods.

All these drains should be checked for operation, as many leaks in the ceilings are apparent from many of these drains.

Thermostat: System on rear wall in the Sales area did not have a cover.

This cover should be installed, or thermostat replaced.

HVAC Filter: The system on page 21.8 had a poorly installed filter.

Filter should be installed properly.

Front warehouse heaters:

Front middle left: Could not locate the thermostats to turn this heater on. Front middle right: Could not locate the thermostats to turn this heater on.

The thermostats need to be located/installed, and these units made to function.

Water Heater Inspection: No inspection sticker found.

Several water heaters did not have an inspection sticker. These should be inspected and

applied.

Faucets/Traps: Many baths had leaking faucets and drains.

All baths should be inspected/repaired before use.

Lights: Many areas had burnt out, not functioning lighting.

This entire facility had many areas that had many of the lights not functioning.

These need to be replaced/repaired.

Ceiling tiles: Many areas had stained/missing ceiling tiles.

This entire facility had many areas that had many ceiling tiles stained or missing.

These need to be replaced/repaired.

System G1 AC unit: Disconnect not mounted upright

or secured, but labeled vertically.

This should be mounted securely.

System 4B disconnect: Disconnect not mounted securely

This should be mounted securely.

Page 65 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Roof units: K2 Bryant, 10 ton, covers off of unit.

L Trane, 5 ton, 9/88. M GE, 2.5 ton, 11/83.

These three systems on the roof appear to not have associated thermostats or areas that need HVAC.

These should be determined to have a system, or disconnected from power and taken out of service.

Front left HVAC system: The York unit outside the paint area under the overhead HVAC system on the pad

is disconnected from power.

This system should be repaired or removed from service.

HR Ducting: Air vent under Bike 2200-2299 is not connected to ductwork, in the middle

of the HR large room.

This system should have the ducting examined for connections.

Lab Office Doors: Wood doors. 2 of 3 wood office doorknobs broke.

These should be repaired.

Eng. 2nd floor Doors: Combo pushbutton door knob would not open.

This combination should be determined or doorknob replaced.

Walls: Many damaged areas throughout plant.

These should be repaired.

Sales Conf Room Floor: Carpet. Wet area in conference room.

This area, along with the utility room behind this wall should have a fan blowing on the floor this is dry. The utility room floor should be cleaned.

Front warehouse break room Floor: Vinyl tile. Concrete under tile swelling under and near coke machine.

This area should be repaired.

Alarm System Devices: Smoke alarms, hand pull stations, flow detectors, valve position

devices, horns, elevator failure, gas cutoff. Status of all of these inputs are unknown.

These devices should be checked for operation after the panel is commissioned.

Riser #2: 1/4/2010. This date was listed after 5/13/10, so likely

should be 1/4/12. No spare sprinkler heads. Painted over labels.

Riser #3: 1/4/2012 No spare sprinkler heads.
Riser #4: 1/4/2012 No spare sprinkler heads.
Riser #5: 1/4/2012 No spare sprinkler heads.

Spare sprinkler heads are required at each riser.

Areas valved incorrectlyOne inactive riser was still pressurized with no valves to

drain/flush this riser and header on a regular basis, next to riser #3.

This riser should be properly removed from service before a leak occurs.

The outside PIV valve should be closed and this header drained.

Page 66 of 70 Client: Client File: SampleIndustrialInspectionReport

Defective Item Summary

This report is issued for the sole use and benefit of the client(s) listed on page 2 of this report. It is valid only at the date and time of this inspection. An inspection does not reveal every problem that exists or ever could exist, but only those observed on the day of the inspection. Others after this date of the report may not and should not rely on the information in this report. Buyer should consult with a qualified contractor in the appropriate trade to determine the best repair methods, estimate costs, and perform any necessary repairs, servicing or maintenance discussed in this report or verbally at the time of the inspection prior to any final date as indicated in any Real Estate sales agreement. Since B and B Inspections does not dismantle equipment or perform invasive inspections or destructive testing, the contractors subsequent examinations may reveal additional required repairs. This summary is not the entire report. The complete report includes additional information of concern to the client. Pictures of Conditional, or Defective item are included in the report. The client must read the complete report to obtain all pertinent information. All suggested repairs should be performed by a qualified person.

Conditional ratings are defined as an item performing its intended function, but is in need of minor repair.

Defective ratings are defined as an item that appears to be sufficiently deficient; unsafe; hazardous or inoperative.

Vegetation: Tree causing damage to fascia between HR and Sales

areas. Fascia supports broken, and no longer secure.

This tree should be trimmed/removed to prevent further damage to this area.

Outdoor lighting: One wallpack for the side walls/doors functioning of at least 16.

One building mounted flood functioning of at least 11.

Two poles with mounted flood lights functioning of at least 4 poles. Pole on left side leaning and conduit damaged. Lot light aiming to roof.

All outdoor lamps should be replaced, or lights repaired.

Steps/rails: Rails missing for the right side patio.

Rails should be supplied for this area.

Outside Electric: Electrical outlets left side not functioning.

Outlet near engineering AC units not GFCI protected. Extension cord near guard shack powered and not GFCI

protected.

The outlets should be made functional with GFCI protection. The extension cord should be

removed.

Hose bibs: Hose bibs had no water left side.

These should be checked for leaks when the water is turned on.

Right side patio awning: Indoor ceiling insulation should not be used outside.

This insulation should be removed.

Siding Misc.: Side exhaust vent bent mount on right side.

This should be repaired/straightened before it falls.

Roof covering: An active leak was found in the HR near the sink area with a

first aid area.

This source of leak should be determined and repaired.

Ventilation: One powered vent on the Engineering roof cover off and not functional.

This should be repaired.

Page 67 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Structure:

Warehouse column damage exists on about 14 columns. Starting at the right front with column A1, and proceeding to I15 at the rear left corner, A1, A4, A8, A9, C14, F4, F12, G14, H6, have holes mostly from fork trucks. The concrete is likely no longer secure under columns G1, G5, H6. Beams are rusted at the bottom to the point of not providing the intended strength at columns C15, E15, I7, and the front right column of the front warehouse.

These poles should be repaired. Many have had concrete poured around the base of the poles likely for when previous damaged pole were repaired.

The columns that are rusting should have steel replaced/welded and determined to be as substantial as the original.

Moisture from outside: The OSB wood wall at the rear of the second warehouse was holding

as much moisture to peg my moisture meter. This is likely from the debris

in the gutters allowing the water to drain into the wall.

The gutters should be cleaned. The wood at the rear of the rear warehouse removed.

Subpanels: Subpanel B and panel to the rear of Panel A missing covers.

Panels throughout this plant are lacking covers. Many missing complete front panels. Many electrical enclosures are not covered.

These occurrences are too extensive to list.

All of the electrical enclosures should have all missing panels/covers installed.

Rear Federal pacific Service: Overhead. Fused disconnect switch blown on the outside pole.

One half of this panel is not powered. This fuse link/knife switch should be replaced by a qualified person after the panel has been determined to be safe.

Main Breaker Size: Not present for the Rear Federal Pacific Panel.

Section 230.70(A)(1) is as follows: "The service disconnecting means shall be installed at a readily accessible location either outside of a building or structure or inside nearest the point of entrance of the service conductors." The fused pole mounted knife switches are the only way to disconnect this panel. A pole mounted fuse link/knife switch is clearly not a readily accessible location.

A main should be provided for this panel, or the panel replaced.

Main Breaker Size: Not present for the Front Federal Pacific Panel.

Section 230.70(A)(1) is as follows: "The service disconnecting means shall be installed at a readily accessible location either outside of a building or structure or inside nearest the point of entrance of the service conductors." The fused pole mounted knife switches are the only way to disconnect this panel.

A pole mounted fuse link/knife switch is clearly not a readily accessible location.

A main should be provided for this panel, or the panel replaced.

Hail Damage: Most AC units have hail damage. The fins that face the rear of the

building on most of the units have hail damage.

These hail damaged areas should be repaired to make the AC units more efficient, or replaced if the damage is too extensive to repair.

HVAC Heaters: The heat did not turn on with many systems. These are shown on pages 19-44. I am

listing the ones that did not heat by the page numbers. When the first system on a page did not work, I listed it as page x.2, the middle unit as page x.5, and the last unit as page

x.8.

Thes 12 systems did not have any heat: 19.2, 20.2, 20.5, 21.8, 22.3. 30.8, 31.2, 32.8, 33.8, 34.2, 39.8, 40.2, 42.9. These systems should be made operational.

Page 68 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012 Warehouse heaters:

Leftmost:Fan only, no heat.2nd from left:Would not turn on.Middle:Thermostat missing.2nd from right:Would not turn on.

Middle row:

Just left of center: Would not turn on. **Center, front:** Fan only, no heat.

Center, rear: One of two fans turned on, no heat.

Front row:

2nd from left: Thermostat missing.2nd from right: Would not turn on.Rightmost: Would not turn on.

These 10 heaters should be repaired and or have the thermostats installed.

Vent Pipes: Cast/PVC. Pipe broke in two at the front left column of the front

warehouse. This is about a 5 inch cast pipe broken in two.

I failed to take a picture of this.

This pipe should be repaired.

Gas lines: A hose ran in the rafters near the left wall of the warehouse.

This appears to be on and from a gas line.

This hose should be removed.

Toilet: Many toilets and urinals were not functioning. Many had the water turned off to them.

Urinal: Many were loose from the floor.

All the toilets and urinals and sinks in the entire plant should be determined to not leak or

repaired.

Lights: Many baths and other rooms had all of the lights burnt out or otherwise not working.

Many areas in this plant had no functioning lights in the entire room. These should be replaced

or repaired.

Electrical: Hand Blower removed with bare wires

that were likely still powered, for the Women's front warehouse break area.

The power should be turned off, and these wires removed. The blower could then be installed.

Water Heater Operation Not on. Leaking feed water plumbing. Front warehouse break area.

This plumbing should be repaired.

Circulation Pump: Not functioning. Front warehouse break area.

This circulation pump should be turned on/repaired.

Sales Bath's Electric The outlet is not GFCI protected.

Bath outlets installed since 1977 should be GFCI protected. This should be installed.

TPRV and **Drain Tube::** CPVC with taped joint. Drain tube is not installed in a safe manner. Sales area water heater.

This TPRV drain tube should be ran to outside or to a floor drain.

Faucets/Traps: Metal/PVC. It appears the drain is leaking inside the wall behind the sink. Sales area sink.

Moisture meter was pegged-over 44%.

This leak should be repaired and the wall repaired.

Page 69 of 70 Client: Client File: SampleIndustrialInspectionReport

December 10, 2012

Lab Exhausts: #2 Exhaust Fan has no controller. Did not work.

This controller should be installed and the fan made operational.

HR Sink Floor: Carpet, many stains and worn areas. Active roof leak in sink area damaging

tiles.

The roof leak should be determined and repaired.

Exit Doors: Several doors chained shut. Left side

warehouse exit door break-in damage.

All doors should be repaired to close and latch securely.

Overhead Doors: Bright orange door on right wall of first warehouse did not operate.

This should be repaired.

Indoor dock lift: Did not function.

This should be repaired.

Alarm Panel at riser #1:

Inspection last performedNo Inspection sticker found.

Insufficiencies corrected Several insufficiencies exist. Bypassed input 16. Flow Switch.

Monitoring Service Provider: NP

Condition of equipment Disconnected from power and from backup battery.

This panel should be made operational and all inputs and outputs determined to be functional.

Alarm Panel at Warehouse:

Inspection last performedNo Inspection sticker found.

This panel should be inspected.

Riser Sales Area: Installed April 1992. No inspection dates found from then.

No dates were found on the gauges.

This riser appears to have never been inspected. This should be done.

The pressure gauges have to be no older than 6 years old. These did not have a date on them.

The gauges should be replaced.

Tone Bells: Riser at Sales Area outside Tone Bell covered with tape

for painting.

This tape should be removed. The alarm bell should be tested regularly.

Fire Extinguishers: I would guess about 10% at the most are all the fire extinguishers that

are installed. No extinguishers had an inspection date more recent

than 2010.

All fire extinguishers should be installed in all marked locations with an annual inspection

tag, along with monthly inspections noted.

Page 70 of 70 Client: Client File: SampleIndustrialInspectionReport